# Thermo-6

**Quality Test for Temperature Control Units** 



More than just Temperature Control Units Just 6etter. Highlights Checking Facility HB-TP180 Highlights Checking Facility HB-TP180 HB-Therm®

# **Quality Test**

### What is being checked?

- → The temperature control units are thoroughly tested for their functionality.
- → The quality inspection includes the verification of important and safety-relevant components.
- → In addition, parameters such as temperature, pressure, and flow are checked.

#### What is needed?

- → Checking facility HB-TP180
- → Measuring device for Pt 100



# Ensuring interchangeability and reproducibility

Ensure that the displayed values match the reality.

Tested temperature control units enable flexible use and reliably meet the specified requirements.

# Increasing production efficiency

The maintenance interval display of the Thermo-6 helps you identify and address deficiencies early.

With tested units, you can rely on your process data and save a lot of time during the startup process.

### Eliminating tolerances

All sensors and probes have their tolerances. Through unit calibration, we ensure that temperature, pressure, and flow values are accurately restored.

# Confirm quality standards

With the checking facility HB-TP180, you ensure that the temperature control units are functioning properly.

The test reports meet all requirements of the Quality Management System (QMS) for documented maintenance.

### Extending service life

The thermal and physical requirements for temperature control units are often extremely high. With minimal maintenance effort, you can significantly extend the lifespan of your temperature control units.

2

Highlights Checking Facility HB-TP180 Highlights Checking Facility HB-TP180

# **Quality Test**

Certainty and consistent quality in any production process demand the documented maintenance of all quality-related equipment. This is also one of the requirements of a quality management system.

The temperature control unit stores the values obtained through the checking facility. For analysis and certificate creation, the data can be transferred to a PC via USB stick and further processed using the VIP software.


Thermo-6 – Housing size 62 with HB-TP180



#### Scope of Testing and Testing procedures

Thermo-6	<ul> <li>→ Visual inspection</li> <li>→ Functional verification based on unit type and configuration</li> </ul>
Commonanto	→ Heating
Components	→ Cooler
-	→ Filling pump
	→ Pressure gauge
	→ Temperature sensors, pressure sensors and acoustic transducers
	→ Safety valve
	→ Heating thermostats
Magaziramanta	→ Temperature measurement using Pt 100 or Type J thermocouple
Measurements	→ Pressure validation via pressure gauge
	→ Flow measurement using differential pressure measurement
	Testing the pump condition using pressure measurement


#### **Testing Principle**



## Calibration

All sensors and probes are subject to tolerances. For temperature sensors, this is  $\pm 3$  °C, and for pressure sensors, it is  $\pm 0.4$  bar. In extreme cases, this can result in a process temperature change of up to 6 °C due to the replacement of a temperature control unit, potentially going unnoticed. For this reason, HB-Therm calibrates each temperature control unit before factory delivery to ensure accurate and consistent measurements.

With the checking facility HB-TP180, we offer you the opportunity to recalibrate the units directly on-site.



#### 35 minutes

#### **Conduct Quality Inspection independently**

Do the displayed values still match the actual measurements?

We recommend checking the units annually. With the checking facility

HB-TP180, you can carry out the verification independently at your company.

The unit automates and largely conducts all testing steps independently, informing the inspector as soon as input or action is required. During the inspection, the remaining time until the next required action is displayed, allowing the inspector to efficiently use their time for other tasks without needing to stay at the unit constantly.

#### **Recalibration of the Temperature Control Unit**

At the end of the automated quality inspection, you have the option to agree to a recalibration defined by Thermo-6. Alternatively, you can perform this later, as the measurement data is stored in the unit.

#### 5 minutes

#### **Creating Test Reports**

The obtained measurement data can be output via the USB interface and processed into a test report using our free VIP program.



## **Example Test Report**

8

Unit under test						
Temp. control unit						
Туре	HB-160Z61-8-4S-A2-400					
No.	2327-077					
Additional equipment	-					
Running hours	6665,3	3				
Software	SW61-	-1_2428				
Test equipment						
Test device						
Туре	HB-TP	180				
No.	PMS36	669				
Last inspect	2023-1	10-01				
Reference measuring equipment						
Туре	Multim	eter				
No.	PMS3	134				
Last inspect	2023-10-13					
Recordings		Ref.	Unit	Diff.	Tol.	Result
Main line temperature						
Temperature 1	°C	39,6	39,6	0,0	± 1,0	Passed
Temperature 2	°C	159,9	159,9	0,0	± 1,0	Passed
Temperature 3	°C					
Temperature 4	°C					
Return line temperature		•	_	_	-	
Temperature 1	°C	39,6	39,6	0,0	± 1,0	Passed
Temperature 2	°C	159,9	159,9	0,0	± 1,0	Passed
Temperature 3	°C					
Temperature 4	°C					
External temperature						
Temperature 1 (Typ J)	°C					
Temperature 2 (Typ J)	°C					
Temperature 3 (Typ J)	°C					
Temperature 4 (Typ J)	°C					
Typ Pt 100	°C					
System pressure						
Pressure 1	bar	0,0	0,0	0,0	± 0,2	Passed
Pressure 2	bar	8,7	8,7	0,0	± 0,2	Passed
Main line pressure						
Pressure 1	bar	0,0	0,1	0,1	± 0,2	Passed
Pressure 2	bar	8,7	8,8	0,1	± 0,2	Passed
Return line pressure						

Unit under test						
Temp. control unit						
Туре	HB-160Z61-8-4S-A2-400					
No.	2327-07	2327-077				
Messungen		Ref.	Unit	Diff.	Tol.	Result
Pressure gauge						
Pressure 1	bar	0,0	0,0	0,0	± 0,5	Passed
Pressure 2	bar	8,7	8,7	0,0	± 0,5	Passed
Flow rate						
Flow rate 1	L/min	0,0	0,0	0,0	± 0,1	Passed
Flow rate 2	L/min	21,1	21,1	0,0	± 1,2	Passed
Pump						
max. pressure	bar	6,7	6,5	-0,2	- 2,0	Passed
Tests						Result
Heater	Heating	up withou	t interruption	n		Passed
Safety valve	Safety v	Safety valve successfully tested		Passed		
Safety test		Safety test done as per instruction and no defects of safety detected.			Passed	
Overall result						
Quality test	Passed					
Remarks	-	-				
Date / Name	2024-08	3-06	John D	ne		

Note:

By default, two predefined test temperatures are set (40 °C and the max. main line temperature). Two additional test temperatures are available if needed. The calibration is based on temperatures 1 and 2 and includes an offset and a slope value. The two additional temperatures are checked to ensure they fall within the tolerance range.

9

HB-TP180 Technical Data

#### Further information

### **Specifications**

Checking Facility	Temperature Control Units Heat transfer medium		Thermo-6	
			Water	
	Housing size		61, 62 (pump 4T/4S)	62 (pump 6P/6R)
Maximum main line temperature		100/140/160°C	100/140/160/180 °C	
Туре			HB-TP180-12	HB-TP180-45
Accessories	Test plug Pt 100	T25320	•	•
	2x laboratory cables 1 m	T25319	•	•
	Cabel Fe-CuNi, 2 m	T25318	•	•
	Adapter R1¼ - M36	T25380		•
	Hose PFA DN25x750	T25390		•
	Calibration certificate		•	•
	Carrying case		•	•

Ordering example: HB-TP180-12, Water, English

Standard specification

Technical Data		HB-TP180-12	HB-TP180-45	
Connection, main line and return line				
Threads of the temperature control unit		G3/4	G1¼	
Resistance	bar, °C	25, 200	25, 200	
Calibration @1bar	L/min	12	45	
Pressure resistance	bar	25	25	
Dimensions Height	mm	232	263	
Width	mm	240	240	
Depth	mm	202	226	
Weight max.	kg	9	9	
Surface temperature °C		>75		
Environment Temperature range	°C	5-60		
Relative humidity		35-85 % RH (non-condensing)		
Standards		EN ISO 12100, EN ISO 13732-1, EN IEC 63000		
Certification/Approval		CE, UKCA		

Testing equipment (not included)	Recommendation
Reference measuring device Pt 100	Gossen Metrawatt (gossenmetrawatt.de)

#### **Quality Test**

With the checking facility HB-TP180, both the temperature control units Thermo-6 and Thermo-5 can be tested. The testing procedure for Thermo-6 is described in detail in our Knowledge database, while the verification of Thermo-5 is explained in the instruction manual of the checking facility.

#### Contents:

- → Thermo-6 test instructions
- → Operating manual for checking facility
- → Unit software Thermo-6



hb.click/ 6-TP180-F

**VIP** 

With the visualisation program VIP, you can create test reports. Transfer the test data from the temperature control unit to your PC via USB stick and import it into the free VIP program.



hb-therm.com

10

### Distributors worldwide



Algeria Argentina Australia Austria Belgium Bolivia

Bosnia and Herzegovina

Brazil
Bulgaria
Chile
China
Colombia
Costa Rica
Crock Bany

Czech Republic Denmark Ecuador El Salvador
Estonia
Finland
France
Germany
Great Britain
Guatemala
Hong Kong
Hungary
India
Indonesia
Ireland
Israel
Italy
Japan

Korea

Latvia

Liechtenstein Lithuania Luxembourg Malaysia Mexico Morocco Netherlands New Zealand North Macedonia **Norway** Paraguay Peru **Poland** Portugal Romania Serbia

Singapore

Slovakia Slovenia South Africa Spain Sweden Switzerland Taiwan Thailand Tunisia Türkiye Uruguay USA Venezuela Vietnam

